



Tel. : 24673815
Fax : 24101053
E-mail : maitreyi1967@yahoo.co.in

MAITREYI COLLEGE

(UNIVERSITY OF DELHI)

BAPU DHAM COMPLEX,
CHANAKYAPURI,
NEW DELHI-110021

"QUOTATION INVITATION FOR CIVIL WORK"

LAST DATE EXTENSION NOTICE

DATED: 09.03.2023

This is hereby informed to all interested parties that the last date of submission of the quotation dated 22.02.2023 for civil work at college has been extended till 15.03.2023.

Interested parties may submit their quotation by 15.03.2023, before 5 PM preferably by hand or by post in a sealed envelope. The envelope must carry the title "Quotation for Civil Work". The quotation must be in the name of Principal, Maitreyi College, University of Delhi, Near Bapu Dham Complex, Chanakyapuri, New Delhi-110021.

Ranu Kumar
Admp. Officer



MAITREYI COLLEGE

(UNIVERSITY OF DELHI)

BAPU DHAM COMPLEX,
CHANAKYAPURI,
NEW DELHI-110021

Ref. No.MT/2023/ 1147-A

Dated:-22.02.2023

WEBSITE

Subject:- INVITATION OF QUOTATION FOR CIVIL WORKS.

Dear Sir,

Sealed Quotations are invited from the eligible and resourceful licensed labor contractors having sufficient experience and equipment's in execution of similar type of jobs as details given below:-

1. Supply installation and fixing flood light including required brackets, fixing arrangement, switch, socket, connection wire etc. complete in all respect (LED 80 watt).
2. Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and Plinth in : Cement mortar 1:4 (1 cement : 4 coarse sand)
3. Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.
4. Providing and laying in Position cement concrete of specified grade including the cost of centering and shuttering – All work up to plinth level: 1:5:10 (1 cement: 5 coarse sand (zone-III) derived from natural source: 10 graded stone aggregate 40mm nominal size.
5. Providing and laying polished granite stone flooring in required design and pattern, in liner as well as curvilinear portion of the building all complete as per the college specification/design with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement: 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polished etc. all complete as specified and as directed by the engineer- in- charge. Polished granite stone slab Zed black, Cherry red, Elite brown, Cat eye or equivalent.
6. Providing and laying 6MM thick synthetic carpet as per sample approved by the college.
7. Covering of existing drain with R.C.C. Slab above 200 mm thick including required shuttering reinforcement etc. complete in all respect.



Tel. : 24673815
Fax : 24101053
E-mail : maitreyi1967@yahoo.co.in

MAITREYI COLLEGE

(UNIVERSITY OF DELHI)

BAPU DHAM COMPLEX,
CHANAKYAPURI,
NEW DELHI-110021

Bid Security/EMD Payment:

Earnest Money Deposit of Rs. 7500/- (seven Thousand five hundred Only) in the form of Bank Draft from any Nationalized Bank in favour of Principal Maitreyi College. Bidders are required to mention the details of EMD in the quotation letter.


Vendors are requested to quote the rates item wise/work wise basis only. All contractors are requested to inspect the site on any working day (10:30 AM to 5:00 PM) before quoting the rates.

The Principal reserves the right to accept or reject some or all the quotations without assigning any reasons thereof.

If however, it is found that the material provided is of sub-standard quality or not as per our specification, the Principal/Committee shall have the right to withhold the payment partly or fully and /or penalty may be imposed on the firm. The decision of the Principal/Committee shall be final and binding on the firm.

The duly sealed quotations must reach the college latest by **08.03.2023**.

Yours faithfully,


Prof. Haritma Chopra
Officiating Principal

